



<b>Name: Hermitano, Johnny C</b>	<b>Date Performed: 12/07/2022</b>
<b>Course/Section: CPE31S23</b>	<b>Date Submitted: 12/07/2022</b>
<b>Instructor: Engr. Jonathan Taylar</b>	<b>Semester and SY: 1st yr sy 2022</b>
<b>Activity 13: OpenStack Prerequisite Installation</b>	
<b>1. Objectives</b>	
Create a workflow to install OpenStack using Ansible as your Infrastructure as Code (IaC).	
<b>2. Intended Learning Outcomes</b>	
<ol style="list-style-type: none"> <li>1. Analyze the advantages and disadvantages of cloud services</li> <li>2. Evaluate different Cloud deployment and service models</li> <li>3. Create a workflow to install and configure OpenStack base services using Ansible as documentation and execution.</li> </ol>	
<b>3. Resources</b>	
<p>Oracle VirtualBox (Hypervisor)</p> <p>1x Ubuntu VM or Centos VM</p>	
<b>4. Tasks</b>	
<ol style="list-style-type: none"> <li>1. Create a new repository for this activity.</li> <li>2. Create a playbook that converts the steps in the following items in <a href="https://docs.openstack.org/install-guide/">https://docs.openstack.org/install-guide/</a> <ol style="list-style-type: none"> <li>a. NTP</li> <li>b. OpenStack packages</li> <li>c. SQL Database</li> <li>d. Message Queue</li> <li>e. Memcached</li> <li>f. Etcd</li> <li>g. Create different plays in installing per server type (controller, compute etc.) and identify it as a group in the Inventory file.</li> <li>h. Add, commit and push it to your GitHub repo.</li> </ol> </li> </ol>	
<b>5. Output (screenshots and explanations)</b>	
Step 1. Create your own github repository to clone.	



Step 2. Clone your repository and start creating your inventory and ansible.cfg

```
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ sudo nano ansible.cfg
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ sudo nano inventory
[sudo] password for jhermitano:
```



```
jhermitano@Workstation: ~  
GNU nano 6.2 ansi  
[defaults]  
  
inventory = inventory  
Host_key_checking = False  
  
depracation_warnings = False  
  
remote_user = jhermitano  
private_key_file = ~/.ssh/
```

Step 3. Create your playbook with this code to install the activities requirements.

```
GNU nano 6.2 install_openstack  
--  
- hosts: all  
  become: true  
  pre_tasks:  
    - name: install ntp, mssql  
      apt:  
        name:  
          - ntp  
          - mysql-server  
  
- hosts: all  
  become: true  
  tasks:  
    - name: update repository index  
      apt:  
        update_cache: yes  
        when: ansible_distribution == "Ubuntu"  
  
    - name: editing the chrony.conf file  
      copy:  
        dest: /etc/chrony/chrony.conf  
        content:  
          server 192.168.56.105  
          allow 10.0.0.0/24  
        mode: 0755  
  
    - name: install openstack package  
      command: snap install --edge microstack --classic  
  
    - name: install etcd  
      apt:  
        name:  
          - etcd  
        state: latest  
  
    - name: install message queue and memcached  
      apt:  
        name:  
          - rabbitmq-server  
          - memcached  
        state: latest
```

Step 4. Run your playbook with this command: `ansible-playbook --ask-become-pass yourPlaybook`

```
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ ansible-playbook --ask-become-pass install_openstack.yml
BECOME password:

PLAY [all] *****

TASK [Gathering Facts] *****
ok: [192.168.56.105]

TASK [install ntp, mssql] *****
changed: [192.168.56.105]

PLAY [all] *****

TASK [Gathering Facts] *****
ok: [192.168.56.105]

TASK [update repository index] *****
changed: [192.168.56.105]

TASK [editing the chrony.conf file] *****
changed: [192.168.56.105]

TASK [install openstack package] *****
changed: [192.168.56.105]

TASK [install etcd] *****
changed: [192.168.56.105]

TASK [install message queue and memcached] *****
changed: [192.168.56.105]

PLAY RECAP *****
192.168.56.105      : ok=8    changed=6    unreachable=0    failed=0    skipped=0    rescued=0    ignored=0

jhermitano@Workstation:~/Hoa_13.1_Portfolio$
```

Step 5. Verify the installation.

```

jhermitano@Server1:~$ memcached --version
memcached 1.6.14
jhermitano@Server1:~$ sudo systemctl status ntp
[sudo] password for jhermitano:
Sorry, try again.
[sudo] password for jhermitano:
● ntp.service - Network Time Service
   Loaded: loaded (/lib/systemd/system/ntp.service; enabled; vendor preset: v
   Active: active (running) since Wed 2022-12-07 10:01:45 PST; 23min ago
     Docs: man:ntpd(8)
    Main PID: 48933 (ntpd)
      Tasks: 2 (limit: 1080)
     Memory: 1.1M
        CPU: 155ms
    CGroup: /system.slice/ntp.service
            └─48933 /usr/sbin/ntpd -p /var/run/ntpd.pid -g -u 136:143

Dec 07 10:01:54 Server1 ntpd[48933]: Soliciting pool server 185.125.190.57
Dec 07 10:01:55 Server1 ntpd[48933]: Soliciting pool server 2620:2d:4000:1::41
Dec 07 10:02:54 Server1 ntpd[48933]: Soliciting pool server 2606:4700:f1::123
Dec 07 10:03:03 Server1 ntpd[48933]: Soliciting pool server 2620:2d:4000:1::3f
Dec 07 10:03:58 Server1 ntpd[48933]: Soliciting pool server 2606:4700:f1::1
Dec 07 10:04:10 Server1 ntpd[48933]: Soliciting pool server 2620:2d:4000:1::40
Dec 07 10:05:02 Server1 ntpd[48933]: Soliciting pool server 2606:4700:f1::123
Dec 07 10:07:25 Server1 ntpd[48933]: kernel reports TIME_ERROR: 0x41: Clock Unv
Dec 07 10:11:45 Server1 ntpd[48933]: 185.125.190.58 local addr 10.0.2.15 -> <n>
Dec 07 10:11:45 Server1 ntpd[48933]: 185.125.190.56 local addr 10.0.2.15 -> <n>
lines 1-21/21 (END)
jhermitano@Server1:~$

```

Step 6. Git add your files. You can use git status to check the status of your file.

```

jhermitano@Workstation:~/Hoa_13.1_Portfolio$ ls
ansible.cfg  install_openstack.yml  inventory
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ git add ansible.cfg inventory install_openstack.yml
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ git status
On branch main

No commits yet

Changes to be committed:
  (use "git rm --cached <file>..." to unstage)
        new file:   ansible.cfg
        new file:   install_openstack.yml
        new file:   inventory

```

Step 7. Git commit and then git push.

```
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ git commit -m done
[main (root-commit) 638149a] done
3 files changed, 58 insertions(+)
create mode 100644 ansible.cfg
create mode 100644 install_openstack.yml
create mode 100644 inventory
jhermitano@Workstation:~/Hoa_13.1_Portfolio$ git push -u origin main
Enumerating objects: 5, done.
Counting objects: 100% (5/5), done.
Compressing objects: 100% (4/4), done.
Writing objects: 100% (5/5), 783 bytes | 783.00 KiB/s, done.
Total 5 (delta 0), reused 0 (delta 0), pack-reused 0
To github.com:jhermitano/Hoa_13.1_Portfolio.git
* [new branch]      main -> main
Branch 'main' set up to track remote branch 'main' from 'origin'.
jhermitano@Workstation:~/Hoa_13.1_Portfolio$
```

Step 8. You verify your files if successfully pushed through your github repository.

The screenshot shows the GitHub interface for the repository 'jhermitano / Hoa\_13.1\_Portfolio'. The repository is public and has 1 branch (main) and 0 tags. The commit history shows a single commit by 'Johnny done' with the message 'done' at 638149a, pushed 1 minute ago. The commit details show three files: 'ansible.cfg', 'install\_openstack.yml', and 'inventory', all marked as 'done' and pushed 1 minute ago. A prompt at the bottom encourages adding a README file to help people understand the project.

### Reflections:

Answer the following:

1. What are the benefits of implementing OpenStack?

**Cloud services can be utilized on any device with internet connectivity, thus there aren't many requirements for using them. high reliability and security**

**for data. scalable storage performance and volume. Cloud-based services promote cooperation. Location is not a barrier to access.**

**Conclusions:**

**In this activity, I successfully achieved the tasks of creating a playbook that installs Openstack using ansible as my IaC. I may have encountered a lot of problems like, the system of my Manage node requires me to fix problems regarding installing through playbook. But then, I successfully fixed it to accomplish this activity.**